

15-007-30255-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

Barber County, Sec. 27 Twp. 32S Rge. 15 (W)  
Ctr. NW NW



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines  
Lease Owner Champlin Petroleum Company  
Lease Name Baird Well No. 5  
Office Address P. O. Box 308, Ellinwood, Kansas 67526  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed July 25 19 66  
Application for plugging filed September 7 19 71  
Application for plugging approved September 8 19 71  
Plugging commenced October 2 19 71  
Plugging completed October 7 19 71  
Reason for abandonment of well or producing formation Uneconomical to produce

If a producing well is abandoned, date of last production September 17 19 71  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 5121 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE      | PUT IN  | PULLED OUT |
|-----------|---------|------|----|-----------|---------|------------|
|           |         |      |    | 8-5/8" OD | 252' OD | None       |
|           |         |      |    | 4 1/2" OD | 3970'   | 2892'      |
|           |         |      |    |           |         |            |
|           |         |      |    |           |         |            |
|           |         |      |    |           |         |            |
|           |         |      |    |           |         |            |
|           |         |      |    |           |         |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 3800' and run 4 sacks cement to 3770' then filled with mud to 270' and set plug, filled with rock to 260' and ran 4 yards of Ready Mix cement filling hole to bottom of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 27 1971  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Glenn & Smith Pipe Pulling Company  
Address Ellinwood, Kansas 67526

STATE OF Kansas, COUNTY OF Barton, ss.  
J. W. Meyers (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Meyers District Operations Manager  
P. O. Box 308, Ellinwood, Kansas (Address)

Subscribed and Sworn to before me this 25th day of October, 1971



N. Kenneth Stivers Notary Public.

DRILLER'S LOG

COMPANY: Champlin Petroleum Company  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: W. F. BAIRD #5  
 LOCATION: C NW NW Sec. 27-32S-15W  
 BARBER COUNTY, KANSAS  
 COMMENCED: 6-2-66  
 COMPLETED: 6-18-66

|      |             |                                |
|------|-------------|--------------------------------|
| 0    | 20          | Shale, Gypsum                  |
| 20   | 233         | Redbed, Sand, Gypsum           |
| 233  | 775         | Redbed                         |
| 775  | 910         | Shale                          |
| 910  | 945         | Anhydrite                      |
| 945  | 1975        | Shale, Shells                  |
| 1975 | 2640        | Lime, Shale                    |
| 2640 | 3320        | Shale, Lime                    |
| 3320 | 4272        | Lime, Shale                    |
| 4272 | 4700        | Lime                           |
| 4700 | 4762        | Lime, Chat                     |
| 4762 | 4796        | Lime, Chert                    |
| 4796 | 4801        | Lime                           |
| 4801 | 4856        | Lime, Shale                    |
| 4856 | 4920        | Lime                           |
| 4920 | 4970        | Lime, Shale                    |
| 4970 | 5067        | Lime                           |
| 5067 | 5121        | Sand, Lime                     |
|      | <u>5121</u> | <u>RTD - Set 4 1/2" Casing</u> |

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 8 - 7 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas

Set 8 5/8" new 20# surface casing @ 244' cemented with 175 sacks  
 Sunset

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the W. F. Baird #5 well, located C NW NW of Section 27, Township 32 South, Range 15 West, Barber County, Kansas, this as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 21st day of June, 1966.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:  
 April 1, 1967