

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED Form CP-4
STATE CORPORATION COMMISSION REV. 12-15-80

FEB 22 1989
2-22-89
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barber SEC. 22 TWP. 30S RGE. 13 E/W
Location as in quarters or footage from lines:
NE/SW/NW

X			

Locate Well
correctly on above
Section Platt.

Lease Owner The National Oil Company (Ohio)
Lease Name Grigsby #2 Well No. _____
Office Address 37 West Broad St., Columbus, Ohio 43215
Character of Well (Completed as Oil, Gas or Dry Hole): Gas
Date Well Completed May 2, 1975
Application for plugging filed November 10, 1988
Plugging commenced January 9, 1989
Plugging completed January 11, 1989
Reason for abandonment of well or producing formation Well bad;
junk in the hole and reservoir was depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Pfifer
Producing formation Lansing Depth to top bottom T.D.
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Marmaton	Oil & Water	4254	4259	4 1/2"		
		4309	4344	4 1/2"		
Lansing	Gas-Water	4039	4044	4 1/2"		
				4 1/2"	4478'	645'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Cement retainer set at 2590' - 50 sacks of 60/40 poz with 6% Gel was squeezed into the well; final pressure 1200 psi; 4-1/2" casing was shot off at 2380'; casing pulled into at 645'; casing was pulled. 200 sacks of 60/40 poz w/6% and 400 lbs of Hulls were used to plug. 15 bbl of water w/200 lbs of hulls followed by 200 sacks of cement with 200# of hulls in the lead cement was pumped into the 8-5/8" casing; final pressure 1500 psi. Cement was checked the following day 1-12-89 and cement was at the surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pratt Well Service, Halliburton Services
Garr Roberts Consulting

STATE OF Ohio COUNTY OF Franklin, ss.
The National Oil Company (Ohio) (~~employee of owner~~) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Kuncak
37 W Broad St, Suite 1100, Columbus, OH
(Address) 43215

SUBSCRIBED AND SWORN TO before me this 17th day of February, 1989

Susan P. House
Notary Public.

My Commission expires _____



13194 SUSAN P. HOUSE
NOTARY PUBLIC, STATE OF OHIO
MY COMMISSION EXPIRES AUG. 31, 1991