

15-007-10297-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME Holmes

WELL NUMBER C-2

400 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 15 TWP. 33S RGE. 13W (E) or (W)

COUNTY Barber

Date Well Completed 9/10/37

Plugging Commenced 9/05/90

Plugging Completed 9/07/90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Chevron U. S. A. Inc.

ADDRESS P. O. Box 36366, Houston, Texas 77236

PHONE# (713) 561-3602 OPERATORS LICENSE NO. 4519

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/07/90 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Misener Depth to Top 4872 Bottom 4887 T.D. 4912

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Misener	gas	4872	4887	13"	272	---
Mississippi Chat	gas	4580	4609	7"	4837	---
				4 1/2" Liner	4480-911	(431') ---

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
CICR @ 4450', 90# mud 4450' to surface, 50 sks Class 'A' cmt (40 thru & 10 on top)
Perf 620-22', couldn't get circ. Set CICR @ 519', pmp/sqz 90 sks Halliburton Lite
thru. Perf 5 hole @ 250', pmp 137 sks Howco Lite to surface

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. N/A

Address P. O. Box 963, Pratt, KS 67124 (316-672-5593)

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chevron U. S. A. Inc., Attn: Sharon L. Houk

STATE OF Texas COUNTY OF Harris, ss.

Sharon L. Houk (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION

(Signature) Sharon L. Houk

(Address) P. O. Box 36366, Houston, TX 77236

SUBSCRIBED AND SWORN TO before me this 8 day of October 1990

10-11-90
CONSERVATION DIVISION
Wichita, Kansas

Joseph J. Huff
Notary Public

My Commission Expires: 2-15-93