

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-32-3-117

15-007-03343-00-01

API NUMBER D&C 06/30/39

LEASE NAME Holmes "C"

WELL NUMBER 3

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

2195 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 15 TWP. 33S RGE. 13 (XX or (W))

COUNTY Barber

LEASE OPERATOR Chevron U.S.A., Inc.

ADDRESS P.O. Box 12116, Oklahoma City, Ok 73157

PHONE# (405) 949-7000 OPERATORS LICENSE NO. 4519

Date Well Completed 06/29/39

Character of Well SWD (Converted to SWD 06/77)

Plugging Commenced 06/10/86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 06/12/86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #1

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation None Depth to Top _____ Bottom T.D. 4969'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippi	Gas	4553	4600	10.75	286	-0-
Misener	Oil	4833	4969	7.00	4833	-0-
				5.50	52	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
 MIRU WSU, POOH w/tbg & seal assembly, TIH & tag pkr @ 4799'. Mix and pmp 150 sx CL "H" w/1% Calcium Chloride. Pull tbg to 4100'. WOC. TIH & tag cmt @ 4140'. Displace hole w/9.0 ppg mud. Perf 7" csg @ 750'. Pmp 425 sx CL "H" cmt. Top off 7" x 10-3/4" annulus and fill 7" csg to surface w/56 sx CL "H" cmt. Cut off csg cap & ID well.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor N/A License No. _____

Address _____

STATE OF _____ COUNTY OF _____, ss.

Michael McCarthy

CONSERVATION DIVISION
 Wichita, Kansas

(Employee of Operator) or (~~operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael O McCarthy

(Address) _____

SUBSCRIBED AND SWORN TO before me this 18th day of JUNE, 1986

Steve R. Wilson
 Notary Public

My Commission Expires: 9-16-86