

15-009-30395-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 28 Twp. 16S Rge. (X) 13 (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Lee Phillips & John Graves
Lease Name Redetzke Well No. 1
Office Address 412 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 27, 19 66
Application for plugging filed March 27, 19 66
Application for plugging approved March 27, 19 66
Plugging commenced March 27, 19 66
Plugging completed March 27, 19 66
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan, Russell, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3200 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	340'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 330 feet. Followed by wooden plug and 1/2 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 13 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1966
4-12-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
Address 412 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
412 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of April, 19 66

My commission expires April 30, 1967 Betty Brandt Notary Public.

15-009-30395-0000

ROTARY DRILLERS' LOG

OPERATOR: Lee Phillips & John Graves DRILLING COMMENCED: March 23, 1966
 412 Union Center
 Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: March 27, 1966
 412 Union Center
 Wichita, Kansas

CASING RECORD: 16 Jts. 340' of 8-5/8" LOCATION: Redetzke No. 1
 cemented with 250 sacks NE NE NE
 Section 28-16S-13W
 Barton County, Kansas

0 - 74 Soil & shale
 74 - 340 Shale & lime
 340 - 600 Shale
 600 - 877 Shale & red bed
 877 - 903 Anhydrite
 903 - 1625 Shale
 1625 - 2044 Lime & shale
 2044 - 2150 Lime with shale streaks
 2150 - 2611 Lime & shale
 2611 - 2704 Lime with shale streaks
 2704 - 2956 Lime & shale
 2956 - 3085 Shale & lime
 3085 - 3093 Lime
 3093 - 3186 Shale, lime & sandy shale
 3186 - 3200 Lime
 3200 Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1966

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves President

STATE OF KANSAS)
) SS:
 BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 11th of April, 1966.

Betty Brandt
 Betty Brandt Notary Public

My commission expires:
 April 30, 1967