

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Finney State Office Building
 130 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-119-20,855-0001

LEASE NAME FOX "G"

WELL NUMBER 1

330 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 13 TWP. 32S RGE 30 (E) or (W)

COUNTY MEADE

Date Well Completed 02/04/93

Plugging Commenced 02/11/97

Plugging Completed 02/16/97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 01/27/97 (date)

by MR. GARY WARDEN (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation UPPER MORROW Depth to Top 5609' Bottom 5630' T.D. 6100'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
U. MORROW	GAS	5609'	5630'	8-5/8"	1621'	4'
				5-1/2"	5745'	2502'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set, MIRU SARGENT & HORTON PLUGGING, INC. PMPD 2 SKS HULLS + 25 SKS CMT 5655-5455' SHOT 5-1/2" CSG @ 3131' - STUCK, SHOT 5-1/2" CSG @ 2502. CIRC MUD PMPD 30 SXS CMT 2500-2400'. PULLED 5-1/2" CSG TO 1660' & PMPD 50 SXS CMT 1660-1510'. PULLED 5-1/2" CSG TO 650'. PMPD 40 SXS CMT 650-550'. PULLED 5-1/2" CSG TO 40'. PMPD 10 SXS CMT 40-0' CUT OF 8-5/8" CSG & CAP 4' BELOW GL. KCC WITNESS GARY WARDEN.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 14th day of April, 1997

My Commission Expires:

FREDA L. HINZ
 Notary Public - State of Kansas
 My Appt. Expires 5-15-99

Notary Public

RECEIVED
 KANSAS CORPORATION
 1997 APR 16
 4-16-97