

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Pratt SEC. 29 TWP. 27S RGE. 11W E/W  
Location as in quarters or footage from lines:  
C NE NE


Locate Well  
correctly on above  
Section Pratt.

Lease Owner Woolsey Petroleum Corporation  
Lease Name Swisher E #1 Well No. \_\_\_\_\_  
Office Address Suite 400 300 W. Douglas Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 8-3-82  
Plugging completed 8-5-82  
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4515'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	1003'	none
				5-1/2"	4077'	2838'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Pumped bottom with 40 sacks cement and pushed plug to 3800'. Shot casing @2816' and  
pulled a total of 67 joints of 5-1/2" casing. Plugged surface with 5 sacks hulls,  
25 sacks gel, 70 sacks cement, released plug and displaced with 80 sacks cement.

Plugging Complete.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 09 1982

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347 Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of August, 19 82



Irene Hoover  
Notary Public.

My Commission expires: \_\_\_\_\_

DRILLERS LOG

No. 1 Swisher "E"

CASING RECORD:	COMPANY:	Woolsey Petroleum Corporation	DESCRIPTION:
8 5/8" @ 1,003' w/450 sx cement	CONTRACTOR:	Red Tiger Drilling Company	C NE/4 NE/4 Sec. 29-T27S-R11W Pratt County, Kansas
5 1/2" @ 4,077' w/200 sx cement	COMMENCED:	March 9, 1981	
	COMPLETED:	April 2, 1981	
TOTAL DEPTH: 4,515'			ELEVATION: 1,779' GR


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Red Bed	0	200	
Red Bed	200	990	
Clay & Red Bed	990	1010	
Shale	1010	1550	
Lime & Shale	1550	4095	
Lime	4095	4105	
Lime & Shale	4105	4515	
RTD		4515	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

  
Gloria Fawcett

Subscribed and sworn to before me this 10th day of April, 1981.

  
Notary Public



281

RECEIVED  
STATE CORPORATION COMMISSION  
JUN - 3 1982  
CONSERVATION DIVISION  
Wichita, Kansas