


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Pratt County. Sec. 29 Twp. 27S Rge. 11W (E) (W)  
Location as "NE/CNW/SW" or footage from lines C SW SE  
Lease Owner C. W. Smith & Associates  
Lease Name Barker Well No. 1  
Office Address 232 Bonnie Brae, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 4-1-66 19  
Application for plugging filed 4-1-66 19  
Application for plugging approved 4-1-66 19  
Plugging commenced 4-1-66 19  
Plugging completed 4-1-66 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas 67124  
Producing formation Depth to top Bottom Total Depth of Well 4417 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	357'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged to 340' with 1/4 sack hulls, 25 sacks cement through drill pipe  
Mudded to 40', set plug, 1/4 sk. hulls, 10 sacks cement  
2 sacks cement in rathole

RECEIVED  
STATE CORPORATION COMMISSION

APR 7 1966

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Leslie Kite

P. O. Box 486, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of April, 1966

Ulanda Nichols

Notary Public.

My commission expires April 1, 1967

Ulanda Nichols

DRILLER'S LOG

COMPANY: C. W. Smith & Associates  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: BARKER #1  
 LOCATION: C SW SE Sec. 29-27S-11W  
 PRATT COUNTY, KANSAS  
 COMMENCED: 3-21-66  
 COMPLETED: 4-1-66

0	138	Sand
138	180	Red Shale
180	841	Redbed
841	1225	Redbed, Shale
1225	1490	Shale
1490	1771	Shale, Shells
1771	2142	Shale, Lime
2142	2450	Shale, Shells
2450	3340	Shale, Lime
3340	3600	Chalky Lime, Shale
3600	4076	Lime
4076	4115	Lime, Chat
4115	4165	Lime
4165	4235	Lime, Shale
4235	4173	Shale
4173	4310	Viola
4310	4393	Lime
4393	4417	Sand
	4417	RTD - D. & A.

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 APR 7 1966  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

Set new 8 5/8" surface casing @ 357' cemented with 250 sacks cement  
 Common, 2% Gel, 3% cc, 50 sacks GL3 with 60# flo seal through all  
 cement

I, Leslie Kite, do hereby certify that the above and foregoing is a  
 true and correct copy of the log of the Barker #1 well, located C SW  
 SE of Section 29, Township 27 South, Range 11 West, Pratt County,  
 Kansas, as reflected by the records of Leben Drilling, Inc.

*Leslie Kite*  
 Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to and before me, a Notary Public, in  
 and for Barton County, Kansas, this 6th day of April, 1966.

*Ulanda Nichols*  
 Ulanda Nichols

My Commission Expires:  
 April 1, 1967