

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,302-00-00

LEASE NAME Fitzsimmons

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

4950 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 27 TWP. 27 RGE. 11 (E) or (W)

COUNTY Pratt

LEASE OPERATOR Pintail Petroleum, LTD

ADDRESS 412 E. Douglas, Suite One, Wichita, Ks. 67202

PHONE 316-687-3450 OPERATORS LICENSE NO. 5086

Date Well Completed _____

Character of Well Oil

Plugging Commenced 9-17-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-23-90

The plugging proposal was approved on September 17, 1990 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom T.D. 4469'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	417'	None
				5-1/2"	4469'	2,799.05'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sant to 3550' and 5 sacks cement. Shot casing at 3100', 2932' and 2800'. Pulled 69 joints of 5-1/2" casing. Howco plugged well with 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls and 100 sacks 60/40 pozmix cement with 6% gel. Maximum pressure 750 psi and shutin 500 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pintail Petroleum, LTD

STATE OF Kansas COUNTY OF Barton, ss.

OCT 26 1990

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 25th day of October, 1990

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-91

Iona M. Leatherman
Notary Public

My Commission Expires: