

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

File All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging of formations.

Pratt County. Sec. 26 Twp. 27S. Rge. 11W/E/ (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. CE/2 SE SW

Lease Owner S. A. Springer

Lease Name T. L. Sitton Well No. 2-B

Office Address 806 Union National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 21, 1942

Application for plugging filed October 11, 1944

Application for plugging approved October 18, 1944

Plugging commenced October 10, 1944

Plugging completed October 15, 1944

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production none 19

Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes  
H. W. Kerr

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3494 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 1/2"	447'	
				5 1/2"	3452'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

This hole was plugged from 3494 feet to 3406 feet with cement. Filled with heavy mud from 3406 feet to 100 feet. Cement bridge from 100 feet to 80 feet. Filled with mud from 80 feet to 15 feet. Bridged and cemented to base of cellar. 447 feet of 8-5/8" pipe cemented and left in hole.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to

Address

STATE OF KANSAS, COUNTY OF SEDGWICK ss.

S. A. Springer (employee of owner) or (owner or operator) of the above-described well,


being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. A. Springer

(Address) Wichita, Kans.

SUBSCRIBED AND SWORN to before me this 10th day of June, 1947

My commission expires November 20, 1948 Notary Public.



Sitton #1B

s/2 SW/4 Sec. 26-27S-11W  
Pratt, County, Kansas

Drilled by S. A. Springer  
Drilled for S. A. Springer

Drilling Commenced: July 28, 1942  
Drilling Completed: August 21, 1942

Casing Record

8 3/4" 447'  
5 1/2" 3452' Cemented

<u>Formation</u>	<u>Depth</u>
Cellar	447
Red Rock & Lime & Shells	670
Shale & Shells	690
Anhydrate	815
Shale & Shells	1120
Salt	1160
Shells & Salt	1210
Shale & Salt	1340
Shale & Lime Broken	1445
Lime & Shale	1545
Shale & Shells	1650
Shale & Sandy Lime	1765
Lime	1875
Lime & Shale	2040
Shale & Shells	2150
Broken Lime	2205
Shale & Lime Broken	2305
Lime	2335
Shale & Shells B. Lime	2430
Lime & Shale	2715
Lime	2755
Broken Lime	2880
Lime	2960
Shale & Shells	3050
Lime & Shale	3195
Lime	3250
Broken Lime	3290
Shale & Lime Shells	3350
Sandy Shale & Lime	3375
Sandy Shale	3442
Lime K. C.	3452
Lime	3494
Total Depth	

Show of Oil 3485 - 94

PLUGGING  
 FILE 26  
 BOOK 35 PAGE 27 LINE 110  
135 LINE 6

