


15-151-10582-00-01

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 19 Twp. 26 Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines. SW SW SE
Lease Owner Wayne E. Walcher
Lease Name Hoener #1 Well No.
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19_____
Application for plugging filed 19_____
Application for plugging approved 19_____
Plugging commenced 7-30-59 19_____
Plugging completed 8-6-59 19_____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19_____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Lackamp 4246
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4345' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	425'	none
				4-1/2"	4345'	2933'
					4246	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed from _____ feet to _____ feet for each plug set.

RECEIVED
STATE CORPORATION COMMISSION

AUG 25 1959
8-25-59
CONSERVATION DIVISION
Kansas

Checked the hole to 4150' and found it open.
Filled w/sand to 4100' and dumped 5 sacks of cement with bailer. Pulled 4 1/2" casing.
Cleaned hole and could not bail fluid off.
Set rock bridge at 350' and dumped 5 sacks of cement. Left set overnight, bailed hole dry and dumped 15 more sacks of cement.
Mudded the hole to 40', set 10' rock bridge and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of August, 1959

My commission expires 9-27-62 Notary Public.


PLUGGING
FILE SEC. 19 T. 26 R. 24
BOOK PAGE 63 LINE 10

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company: NAT'L COOP. REFG. ASSOC. & TRANSIT CORP. SEC. 19 T. 26 R. 12T
Farm: Hooper No. 1 SW SW SE

Total Depth. 4442
Comm. 4-30-52 Comp. 5-21-52
Shot or Treated.
Contractor.
Issued. 6-14-52

County Pratt KANSAS



Elevation. 1924

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	210
red bed & shells	830
shale & shells	1695
lime & shale	1755
lime	2082
sandy lime & shale	2265
lime & shale	2385
lime & sand	2465
shale, lime, shells	2625
shale, lime, shells	
salt	2795
shale	2922
lime & shale	3070
shale	3135
lime brkn & shale	3280
lime & shale	3810
lime	4070
chert & lime	4110
lime	4125
lime & chert	4211
simpson shale & sand	4242
sand & shale	4305
shale	4327
shale & lime	4349
arbuckle lime	4442
Total Depth	

Scout Tops:	
Brown Lime	3687
Lansing	3707
Miss. Lime	4083
Arbuckle	4342
Viola	4131
Simpson	4211

RECEIVED
STATE CORPORATION COMMISSION

SEP 1 1959
9-1-59
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 19 T 26 R 2W
BOOK PAGE 63 LINE 10