

~~5-151-19044-00-01~~


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 21 Twp. 26S Rge. 12 (E) (W) X

Location as "NE/CNW%SW%" or footage from lines. SW SW SE  
Lease Owner R. W. Rine Drilling Company  
Lease Name DeWerff Gas Unit Well No. 1  
Office Address P. O. Box 152 Pratt, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 3-6-65 19  
Plugging completed 3-9-65 19  
Reason for abandonment of well or producing formation  
Dry  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation Depth to top Bottom Total Depth of Well PB 2563 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	449	None
				5 1/2	None	1100

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Cleaned out cellar. Set over night plug at 250', with 5 sacks of cement. Working pipe. Shot pipe at 1600'.

Working pipe. Shot pipe at 1500' - 1400' - 1300' - 1200' and 1090'. Fishing out shooting line. Pulling pipe.

Bailed to 275' rock bridge. Dumped 30 sacks of cement. Filled hole and rock bridge. Capped well with 15 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 17 1965

3-17-65  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
J. O. Forbes

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of March, 1965

My commission expires May 27, 1965

Notary Public.


~~Knop~~ Well No. 1  
Changed to  
DE WERT # 1

SW SW SE  
Sec. 21-26S-12W  
Pratt County, Kansas

Contractor: The R. W. Rine Drilling Company  
Commenced: January 11, 1945

Completed: February 9, 1945

Clay & sand	0- 160	
Sand & shale	160-386	10 3/4" casing cemented @449'
Red Bed	386- 455	
Shale & lime	455- 991	
Red Bed & Shale	991-1295	
Shale & Lime	1295-1740	
Lime	1740-1797	
Lime & Shale	1797-1897	
Shale	1897-1955	
Lime & Shale	1955-2007	
Lime	2007-2045	
Lime & shale	2045-2195	
Lime	2195-2256	
Lime & Shale	2256-2342	
Lime	2342-2520	
Shale & Lime	2520-2795	
Shale & Shells	2795-2910	
Lime	2910-2957	
Lime & Shale	2957-3085	
Shale & shells	3085-3160	
Lime	3160-3193	
Shale & Lime	3193-3220	
Lime	3220-3348	
Lime & Shale	3348-3430	
Shale	3430-3480	
Lime & Shale	3480-3614	
Shale	3614-3667	
Lime & Shale	3667-3758	
Lime	3758-4179	
Shale & shells	4179-4198	
Lime & chert	4198-4217	
Lime	4217-4240	
Lime & Shale	4240-4263	
Lime & Shale	4263-4293	
Sand	4293-4300	
Sand & shale	4300-4321	
Lime & Shale	4321-4330	
Lime	4330-4336	
Shale	4336-4352	
Lime & Shale	4352-4360	
Lime	4360-4367	
Core	4367-4380	5 1/2" casing cemented @4338'
Lime	4380-4426	Total Depth 4426'



21 26 120  
19 40

State of Kansas )  
County of Barton) ss

I, Clyde W. Goddard, do hereby certify that the above is a true and complete log of the Knop Well No. 1, located in the SW of the SW of the SE of Section 21, Township 26S, Range 12W, in Pratt County, Kansas.

Clyde W. Goddard

Sworn to and subscribed before me this 14th day of February, 1945.

Helen L. Williams

My commission expires December 6, 1948