

LEASE NAME Howell

1-24

WELL NUMBER

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

2310 Ft. from S Section Line

2310 Ft. from E Section Line

LEASE OPERATOR Deutsch Oil Co./Dominion Oil & Gas Corp SEC. 24 TWP. 26 RGE. 12W (E) or (W)

ADDRESS 107 N. Market, Su. 1115 Wichita, Kansas 67202 COUNTY Pratt

PHONE# (316) 267-7551 OPERATORS LICENSE NO. 3180/30224 Date Well Completed 9-12-90

Character of Well Oil Plugging Commenced 9-15-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 9-20-93

The plugging proposal was approved on 8-27-93 (date)

by Lacy (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation Mississippi Depth to Top 4060 Bottom 4096 T.D. 4200

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface	sh/lm	0	272	8 5/8	272	None
Productin	ls/sh	0	4194	4 1/2	4194	2258'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid wa placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Fill sand from TD to 3400 ft. Set 4 sx. cement plug at 3400 ft.
Pump 3 sx. hulls, 10 sx. gel., 50 sx. 60/40 poz., 6% gel. cement, 10 sx. gel., 1 sx. hulls, wiper plug, and 100 sx. 60/40 poz., 6% gel. cement down 8 5/8" surface casing.

Name of Plugging Contractor DS&W Well Servicing Inc. License No. 6901

Address P.O. Box 231 Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Deutsch Oil Company/Dominion Oil & Gas

STATE OF Kansas COUNTY OF Sedgwick, ss.

Kent Deutsch

(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed tha the same are correct, so help me God.

RECEIVED

KANSAS CORPORATION COMMISSION

11-24-93

NOV 24 1993

(Signature) [Signature]

(Address) 107 N. Market, Su. 1115
Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 24 day of Nov., 1993

CONSERVATION DIVISION
 WICHITA, KS

My Commission Expires: 7/7/97

[Signature]
 Notary Public

