

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 22 TWP. 26S RGE. 12W E/W
Location as in quarters or footage from lines:
C SE SE

Locate Well
correctly on above
Section Pratt.

Lease Owner Argonaut Energy Corporation
Lease Name Strong #1 Well No. _____
Office Address P O Box 4060, Amarillo, ~~TX~~ Texas 79106
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 5/11/81
Plugging completed 6/18/81
Reason for abandonment of well or producing formation _____

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ bottom T.D. 4500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	411	None
				4 1/2"	4165	2083

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved onto location. Pushed plug to 3850, ran sand and 4 sacks cement. Pulled 18" stretch. Shot and worked pipe at 3025, 2872, 2750, 2625, 2501, 2377, 2250 and 2080. Got loose and pulled total of 51 joints. Plugged well with 15 sacks gel, 8 sacks hulls, 10 sacks gel and 125 sacks cement 4% gel 3% cc. Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING

RECEIVED
STATE CORPORATION COMMISSION
6-25-81
JUN 25 1981
CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 1981

My Commission expires:



Joan Kelso
Notary Public.

15-151-20854-0000
WELL LOG

COMPANY Argonaut Energy Corporation

SEC. 22 T. 26S R. 12W

FARM Strong NO. 1


LOC. C SE SE

TOTAL DEPTH 4500 RTD

COUNTY Pratt, Kansas

COMM. 1-30-81 COMP. 2-10-81

CONTRACTOR DaMac Drilling Inc.



CASING 8 5/8 set 2-411

ELEVATION

PRODUCTION 4 1/2 set @ 4165

FIGURES INDICATE BOTTOM OF FORMATIONS

RedBed, Shale	0	1000
Shale	1000	1967
Lime, Shale	1967	4500 RTD

RECEIVED
STATE CORPORATION COMMISSION
APR 13 1981
4-13-81
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } SS


I, Martha J. McKown of DaMac Drilling Inc.

upon oath state the above and foregoing is a true and correct copy of the log of the Strong No. 1 well.

Martha J. McKown

Subscribed and sworn to before me this 11th day of Feb. 19 81

My Commission Expires:



Wade J. Sullivan
NOTARY PUBLIC