

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-21635-0000

LEASE NAME Strong

WELL NUMBER B-1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

         Ft. from S Section Line

         Ft. from E Section Line  
SW SW SE

SEC. 22 TWP. 26S RGE. 12W (E) or (W)

COUNTY Pratt

LEASE OPERATOR Steve Jones

ADDRESS 112 North Grove St. John, Kansas 67576

PHONE# (316) 549-6189 OPERATORS LICENSE NO. 30116

Date Well Completed         

Character of Well Oil

Plugging Commenced 5-4-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-13-93

The plugging proposal was approved on          (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4520'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	348'	none
				5-1/2"	4520'	3039'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set. Plugged off bottom with sand to 4375' and 5 sacks cement. Shot pipe loose @3039'. Plugged surface with 300# hulls, 10 sks. gel, 50 sks. cement, 10 sks. gel, 100# hulls, plug and 125 sks. of 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kelso Casing Pulling, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of          facts, statements, and matters herein contained and the log of the above-described well as          the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 19th day of May, 19 93

Irene Herzberg  
Notary Public

My Commission Expires:         



RECEIVED  
STATE CORPORATION COMMISSION  
5-20-93  
MAY 20 1993  
CONSERVATION DIVISION  
Wichita, Kansas