

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit


Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 26 Twp. 26 Rge. 12 (E) W (W)

Location as "NE/CNW&SW" or footage from lines NW NW NE  
Lease Owner Lee Phillips Oil Co.  
Lease Name Long Well No. 1  
Office Address 1107 Union National Bank Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 20 19 56  
Application for plugging filed March 20 19 56  
Application for plugging approved March 20 verbally 19 56  
Plugging commenced March 20 19 56  
Plugging completed March 20 19 56  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives, Box 8, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4420 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	336	8 5/8"	336	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud from total depth to 300' with plug set at 300' and 20 sacks of cement on plug. Mud to 35' with plug set and 10 sacks of cement on plug.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 23 1956  
3-28-56  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Harms-Burt Drilling Co.  
Address Box 184, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
Allan Harms (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms  
Box 184, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of March 19 56

My commission expires 1-20-58

Mary E Van Pelt  
Notary Public.

PLUGGING  
FILE SEC 26 T 26 R 12 W  
BOOK PAGE 47 LINE 19

Driller's Log

Company: Lee Phillips Oil Company  
Farm: Long No. 1  
Commenced: February 27, 1956  
Elevation:

NW NW NE Section 26-26-12W Pratt County, Kansas  
Completed: March 20, 1956

0 - 65	Soil & clay	3974- 4015	Shale & lime
65 - 220	Sand & shale	4015- 4066	Lime & shale
220 - 336	Red bed	4066- 4090	Lime & chert
336 - 620	Red bed & shale	4090- 4201	Lime
620 - 655	Shale	4201- 4208	Chert (Viola)
655 - 677	Anhydrite	4208- 4215	Lime & chert
677 - 1150	Shale & shells	4215- 4222	Shale
1150 - 1181	Anhydrite	4222- 4271	Shale & lime
1181 - 1660	Shale & shells	4271- 4297	Lime & shale
1660 - 1845	Lime & shale	4297- 4315	Shale & sand
1845 - 2215	Lime	4315- 4334	Sand & shale
2215 - 3165	Shale & Lime	4334- 4355	Shale & sand
3165 - 3280	Lime & shale	4355- 4380	Sand & shale
3280 - 3398	Lime	4380- 4420	Lime
3398 - 3590	Shale & lime	4420-	T.D.
3590 - 3631	Shale		
3631 - 3974	Lime (B/KC)		

Set 336' of 8 5/8" surface pipe. Cemented with 300 sacks of common cement and 6 sacks of calcium chloride. Pumped 100 sacks of common cement around outside of pipe.

Tops: Anhydrite 1150  
Base of K.C. 3974  
Viola 4201  
Arbuckle 4380

Drill Stem Test: No. 1 4208 - Lost circulation, open 1 hr. shut in 20 min. Recovered 55' mud. 720# BHP  
No. 2 4315 - Could not reach bottom.

Ran electric log. Dry, plugged and abandoned.

Affidavit: State of Kansas )  
County of Barton ) SS

I, Allan Harms of HARMS-BURT DRILLING Co.

being first sworn on oath state: I have knowledge of the facts, statements, and matters herein contained and the same are true and correct.

Signed *Allan Harms*

Subscribed and sworn to before me this 27 day of March 1956.

Comm. Exp. 1-20-58

*Mary E Van Belt*  
Notary Public

MISSION

MAR 23 1956  
3-23-56  
CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
WELL SEC 26 T 26 R 12W  
BOOK PAGE 47 LINE 19