

15-151-10661-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Pratt County. Sec. 28 Twp. 26S Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW/4

Lease Owner Shell Oil Company

Lease Name Hoeme Well No. 4

Office Address 1200 First National Building Oklahoma City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 11-4-66 19

Plugging completed 11-11-66 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie V. Elving

Producing formation Depth to top Bottom Total Depth of Well 4305 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	795	None
				4 1/2	None	1838

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in.

Waiting on Shell - killing gas. Pulled tubing. Pumped 100 sacks of cement, to 2500'.

Cleaned out cellar. Breaking cement. Rigged up. Working pipe.

Put on control head. Working pipe. Shot pipe at 2000' = 1900' and 1830'. Pulling pipe.

Finished pulling pipe. Circulating mud. Squeezed well with 35 sacks of mud and 100 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 21 day of November 1966

My commission expires

May 27, 1969

Notary Public.

NOV 22 1966
11-22-66
CONSERVATION DIVISION
Wichita, Kansas

Shell Oil Company
 O. H. Hoeme No. 4
 SW NE NW Section 28-26S-12W
 Iuka Carmi Field
 Pratt County, Kansas

Commenced: 8-18-44
 Completed: 10-2-44

Casing Set: 8 5/8" set at 795' with 400 sacks cement.
 4 1/2" set at 4293' with 600 sacks mixed with 2% Aquagel & 1/2# Flocele.

Producing Strata: Lansing-Kc ("H" & "I") 3691 - 3715

Well Log:

0	146	Sand, soil & shale
146	590	Red bed
590	638	Sand & gravel
638	950	Red bed
950	1090	Shale & red bed
1090	1235	Shale & shells
1235	1535	Shale & salt
1535	1720	Shale & shells
1720	1760	Anhydrite
1760	2193	Lime & shale
2193	2249	Lime & chert
2249	2305	Lime & shale
2305	2359	Lime
2359	3138	Lime & shale
3138	3579	Lime
3579	3660	Lime & shale
3660	3704	Lime
3704	3820	Lime & shale
3820	3863	Lime
3863	3936	Lime & chert
3936	4082	Lime
4082	4194	Lime & chert
4194	4206	Sand & shale
4206	4235	Sand & lime
4235	4239	Shale & sand
4239	4296	Lime & shale
4296	4305	Dolomite
	4305	Total Depth
	3800	PBTD (CIBP)

RECEIVED
 STATE CORPORATION COMMISSION

OCT 18 1966
 10-18-66
 CONSERVATION DIVISION
 Wichita, Kansas