

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25813-00-00
Spot: NWNESENE Sec/Twnshp/Rge: 15-19S-22W
1416 feet from N Section Line, 551 feet from E Section Line
Lease Name: KLEWENO-KLEWENO Well #: 1
County: NESS Total Vertical Depth: 4430 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	678		WITH 425 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/25/2014 9:15 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: WILLY WYNN Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 710' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 30 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 09/25/2014 11:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 710' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 30 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
OCT - 9 2014
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

OCT 15 2014

CONSERVATION DIVISION
WICHITA, KS

10/15/14 CCM SR

Form CP-2/3