

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22404-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 14-30S-14W  
330 feet from N Section Line, 2260 feet from E Section Line  
Lease Name: MCKENZIE Well #: 1  
County: BARBER Total Vertical Depth: 4849 feet

Operator License No.: 31191  
Op Name: R & B OIL & GAS, INC.  
Address: 124 N MAIN PO BOX 195  
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4834	2200	WITH 200 SX CMT
SURF	10.75	212		WITH 170 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/09/2014 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 35 SX CMT & 250# HULLS. PLUG AT 780' WITH 10 SX GEL & 50 SX CMT. PLUG AT 240' WITH 100 SX CMT. PLUG AT 40' WITH 40 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE  
Date/Time Plugging Completed: 09/09/2014 1:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMP 35 SX CMT WITH 250# HULLS AT 4400'. 1ST PLUG AT 780' WITH 10 SX GEL & 100 SX CMT. 2ND PLUG AT 240' WITH 100 SX CMT. 3RD PLUG AT 40' WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4473	4484		
4446	4470		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

RECEIVED  
OCT - 8 2014  
KCC DODGE CITY

Signed [Signature]  
(TECHNICIAN)  
Received  
KANSAS CORPORATION COMMISSION  
OCT 15 2014  
CONSERVATION DIVISION  
WICHITA, KS

10/15/14 CRM

[Signature]