

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22588-00-00
Spot: NWSE Sec/Twnshp/Rge: 11-30S-14W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: STAATS Well #: 2
County: BARBER Total Vertical Depth: 4780 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 124 N MAIN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4630		
PROD	4.5	4769	2335	WITH 175 SX CMT
SURF	10.75	221		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/15/2014 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SQUEEZE PERFS WITH 30 SX CMT & 100# HULLS. PLUG AT 780' WITH 10 SX GEL & 50 SX CMT. PLUG AT 240' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 09/15/2014 3:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

PUMPED 100# HULLS WITH 30 SX CMT. 1ST PLUG AT 780' WITH 10 SX GEL & 100 SX CMT. 2ND PLUG AT 240' WITH 100 SX CMT. 3RD PLUG AT 40' WITH 40 SX CMT. TOPPED OFF WITH 15 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4678	4682		
4448	4454		
4438	4448		
4426	4438		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

OCT 15 2014

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
OCT - 8 2014
KCC DODGE CITY

Form CP-2/3