

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-22099-00-00  
Spot: S2SESENE Sec/Twnshp/Rge: 5-26S-11W  
2550 feet from N Section Line, 330 feet from E Section Line,  
Lease Name: RUNDELL Well #: 11  
County: PRATT Total Vertical Depth: 4248 feet

Operator License No.: 5046  
Op Name: RAYMOND OIL COMPANY, INC.  
Address: PO BOX 48788  
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4029		WITH 2 SX CMT
PROD	5.5	4233	1373	WITH 175 SX CMT
SURF	10.75	250		WITH 250 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/22/2014 4:00 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS. PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. PLUG AT 270' WITH 100 SX CMT. PLUG AT 60' WITH 40 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE  
Date/Time Plugging Completed: 09/22/2014 5:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4029' WITH 2 SX CMT. 1ST PLUG AT 676' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 290' WITH 100 SX CMT. 3RD PLUG AT 64' WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4102	4118		
4079	4092		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
OCT - 8 2014  
KCC DODGE CITY MD

Received  
KANSAS CORPORATION COMMISSION  
OCT 15 2014  
CONSERVATION DIVISION  
WICHITA, KS

10/15/14 cm ST  
Form CP-2/3