

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-22218-00-00
Spot: NENENW Sec/Twnshp/Rge: 19-12S-28W
400 feet from N Section Line, 2340 feet from W Section Line
Lease Name: KUHN UNIT Well #: 1
County: GOVE Total Vertical Depth: 4625 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	254		170 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/07/2014 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: WILLY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 240 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: NONE
Date/Time Plugging Completed: 10/07/2014 4:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

1st plug @2285 w/50 sx
2nd plug @1360 w/100 sx
3rd plug @310 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: ALLIED
Plugged through: DP

Received
KANSAS CORPORATION COMMISSION
OCT 15 2014
CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Darrel Dipman
(TECHNICIAN) CM
10/15/14 cm

OCT 08 2014