

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21646-00-00
Spot: SENWSW Sec/Twnshp/Rge: 1-23S-19W
1650 feet from S Section Line, 990 feet from W Section Line
Lease Name: HXP1 Well #: 1
County: EDWARDS Total Vertical Depth: 4665 feet

Operator License No.: 30337
Op Name: SPECIAL ENERGY CORP.
Address: PO DRAWER 369
STILLWATER, OK 74076

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	845		WITH 325 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/16/2014 12:00 AM

Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC

Proposal Rcvd. from: GEROGE UTLEY Company: SPECIAL ENERGY Phone: (405) 377-1177

Proposed Plugging Method: 1ST PLUG AT 1350' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 50 SX CMT. 3RD PLUG AT 360' WITH 40 SX CMT. 4TH PLUG AT 60 WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN
Date/Time Plugging Completed: 09/17/2014 12:00 AM

Witness Type: NONE
KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 1350' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 50 SX CMT. 3RD PLUG AT 360' WITH 40 SX CMT. 4TH PLUG AT 60 WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
OCT - 9 2014
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

OCT 15 2014
CONSERVATION DIVISION
WICHITA, KS

10/15/14 ckm

[Signature]