

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-001-03807-0000
 Spot: NWNWNE Sec 24 Twp 26 S Rng 20 ☒ E / ☐ W
4671 Feet from ☐ N / ☒ S Line of Section
2295 Feet from ☒ E / ☐ W Line of Section
 GPS: Lat: 37.774510 Long: 95.168390 Date: 4/30/14 2/13/12
 Lease Name: Beggs II Well #: BEG 10
 County: Allen Total Vertical Depth: 440 feet

Operator License No: 101 String Size Depth Pulled Comments
 Op Name: State of Kansas DRIVE - Drive Pipe 8 000 20 0 EST.
 Address 1: 130 S. Market
 Address 2:
 City: Wichita
 State: Ks Zip Code: 67202 -

Well Type: OG - Oil & Gas (Oil) UIC Docket No.: Date/Time to Plug: 4/9/14 /
 Plug Co License No.: 6372 Plug Co. Name: Splane Pulling and Roustabout Services, Inc.
 Proposal Recvd from: Keith Splane Company Name: SAME Phone: (620) 431-1359

Proposed
Plugging
Report:

Clean out well to TD. Perforate in at least two depths if not documented Alt. II. Pump Portland cement from TD to surface.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: ZERO - None
 Date/Time Plugging Completed: 4/9/14 / KCC Agent: Frank Guilfoyle

Actual Plugging Report: Perfs: Top Bottom Thru
 Move drill rig to location, set up, dig and fill pit. Drill through rocks, wood and cave to 440 ft. Hit cement and steel at 440 ft. Pull drill steel and bit. Run 1" to 440 ft. Pump Portland cement from 440 ft to surface. Pull pipe and top off well. Pump total of 145 sacks of cement. Well plugged.

Remarks: Contract # 37622. Control # 20130030-010. GPS NAD 27. Regular Section. GPS'ed by X Tony A.

Plugged Thru: TBG - Tubing RECEIVED KANSAS CORPORATION COMMISSION
 District: 03 MAY 02 2014 Frank Guilfoyle (Technician)
 Form: District Plugging Report -

CONSERVATION DIVISION
WICHITA, KS