

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-001-02940-0000
 Spot: NWSWNE Sec 24 Twp 26 S Rng 20 ☒ E / ☐ W
3955 Feet from ☐ N / ☒ S Line of Section
2242 Feet from ☒ E / ☐ W Line of Section
 GPS: Lat: 37.772543 Long: 95.168222 Date: 4/11/14 2/13/12
 Lease Name: Beggs II Well #: BEG 13 (P10)
 County: Allen Total Vertical Depth: 750 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>State of Kansas</u>	<u>SURF - Casing</u>	<u>6.250</u>	<u>20</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>130 S. Market</u>	<u>STRL - Casing</u>	<u>2.500</u>	<u>750</u>	<u>0</u>	
Address 2:					
City: <u>Wichita</u>					
State: <u>Ks</u> Zip Code: <u>67202</u> -					

Well Type: EOR - Enhanced Oil Recovery - Injection UIC Docket No.: _____ Date/Time to Plug: 3/24/14 / _____
 Plug Co License No.: 6372 Plug Co. Name: Splane Pulling and Roustabout Services, Inc.
 Proposal Rcvd from: Keith Splane Company Name: SAME Phone: (620) 431-1359

Proposed Plugging Report: Clean out well to TD. Perforate in at least two depths if not documented Alt. II. Pump Portland cement from TD to surface.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: ZERO - None
 Date/Time Plugging Completed: 3/24/14 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Clear around location. Drill 1" and bit by hand to 175 ft and bridged off. Wash and spud to 525 ft. Pull 1" out. Perforate casing. Run 1" to 700 ft. Pump Portland cement from TD to surface. Pull pipe and top off well. Squeeze well with cement and shut in at 300 PSI. Pump total of 30 sacks of cement. Well plugged.		<u>175</u>	<u>300</u>	<u>CSG - Casing</u>

Remarks: Contract # 37622. Control # 20130030-013. GPS NAD 27. Regular Section. GPS'ed by Tony A.

Plugged Thru: TBG - Tubing RECEIVED KANSAS CORPORATION COMMISSION
 District: 03 APR 02 2014
 Plugged Due to Compliance Issue: ☐ Yes ☒ No
 (Technician)
 Form: District Plugging Report -