

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-059-23083 - 0000
Spot: NWSESW Sec 9 Twp 17 S Rng 21 [X] E / [ ] W
842 Feet from [ ] N / [X] S Line of Section
3415 Feet from [X] E / [ ] W Line of Section
GPS: Lat: 38.581500 Long: 95.095720 Date: 3/20/13
Lease Name: AUBRY Well #: AUB 08
County: Franklin Total Vertical Depth: 500 feet

Operator License No: 101
Op Name: State of Kansas
Address 1: 130 S. MARKET
Address 2:
City: WICHITA
State: KS Zip Code: 67202
String Size Depth Pulled Comments
SURF - Casing 6.000 20 0 EST.
PROD - Casing 2.500 500 0 EST.

Well Type: OG - Oil & Gas (oil)
UIC Docket No.: Date/Time to Plug: 2/12/14 /
Plug Co License No.: 3097 Plug Co. Name: K-W OIL WELL SERVICES, INC.
Proposal Rcvd from: Jim Kepley Company Name: K-W Phone: (620) 431-2285

Fill well with portland cement from TD to surface.

Proposed Plugging Report:

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
Date/Time Plugging Completed: 2/12/14 / KCC Agent: Frank Guilfoyle

Actual Plugging Report: Perfs: Top Bottom Thru
75 350 CSG - Casing
Clear trees and brush from around well for equipment access. Run 1" to 350 ft and pull out. Perforate well. Run 1" to 500 ft. Pump Portland cement from TD to surface. Pull pipe and top off well. Pump total of 26 sacks of cement. Well plugged.

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 06 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: Purchase Order No. 38164 Control No. 20130078-008. Irreg. Section. GPS'ed by F.G., T.A., 3-20-13.
NAD83

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: [ ] Yes [X] No

District: 03

Signature (Technician)