

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-003-02 529-0000

Spot: NENESESW Sec 34 Twp 20 S Rng 19 ☒ E / ☐ W
1298 Feet from ☐ N / ☒ S Line of Section
2814 Feet from ☒ E / ☐ W Line of Section

GPS: Lat: 38.262805 Long: 95.296229 Date: 7/30/14

Lease Name: Betty Lybarger Well #: LYB 02

County: Anderson Total Vertical Depth: 525 feet

Operator License No: 101 String Size Depth Pulled Comments
 Op Name: STATE OF KANSAS DRIVE - Drive Pipe 11.000 15 0 EST
 Address 1: 130 S. MARKET
 Address 2:
 City: WICHITA
 State: KS Zip Code: 67202 -

Well Type: OG - Oil & Gas (OIL) UIC Docket No.: Date/Time to Plug: 7/7/14 /
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: Mike Lyday Company Name: KWS Phone: (620) 431-8945

Proposed
Plugging
Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 7/7/14 / KCC Agent: Frank Guilfoyle

Actual Plugging Report: Perfs: Top Bottom Thru

Clear trees and brush from location. Move equipment to location. Run 1" and hit mud at 10 ft. Work 1" to 50 ft. Wash 1" to 525 ft. Pipe kept hanging up. Washing up cuttings. Pump Portland cement from 525 ft to surface. Pull pipe and top off well. Pump total of 214 sacks of cement. Well plugged.

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 05 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: Contract # 38595. Control # 20140065-002. GPS'ed NAD 83 by F. G. Regular section. Category II.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: ☐ Yes ☒ No

District: 03

Frank Guilfoyle
(Technician)

Form: District Plugging Report -