

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 6-28

LOCATION SW-NE-NW

SEC. 18 TWP. 20 RGE. 12 W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 3 Lease Huschka

Operator Bay Pits Co. Address Chase Kansas

Field _____ County Barton

Total Depth 3440 Feet.

Plugging Contractor West Supply Co.

Plugging Contractor's License No. 14

Address Chase Kansas

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 7/8" @ 355' C.W.C. Oil string 5 1/2" @
3440' w/150 SX Cem. L.W.P. 3185' Top Perf. 3176'

Filled Casing back with sand to 3170' and
dumped 5 SX of Cem. with dump bailer. Shot
off and pulled 5 1/2" casing @ approx 2500'. Filled
hole with heavy mud to 300' set rock bridge
and mixed and run 20 SX of Cem. mud to 35'
rock bridge and 10 SX mixed Cem. to base of cellar.

PLUGGING
FILE SEC 18 TWP 20 RGE 12 W
BOOK 6 PAGE 28

RECEIVED
DISTRICT CONSERVATION AGENT
JAN 15 1954
DIVISION
KANSAS

Warren H. Warner
District Conservation Agent

Date 1-13-54