

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21910-00-00
Spot: NWNESWSE Sec/Twnshp/Rge: 21-22S-21W
1136 feet from S Section Line, 1658 feet from E Section Line
Lease Name: DAVID Well #: 1-21
County: HODGEMAN Total Vertical Depth: 4550 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1127		WITH 650 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/06/2014 11:05 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: KEN MCGUIRE Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: IST PLUG AT 1350' WITH 50 SX CMT. 2ND PLUG AT 1140' WITH 50 SX CMT. 3RD PLUG AT 450' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 09/06/2014 2:15 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

IST PLUG AT 1350' WITH 50 SX CMT. 2ND PLUG AT 1140' WITH 50 SX CMT. 3RD PLUG AT 450' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
OCT - 9 2014
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
OCT 15 2014
CONSERVATION DIVISION
WICHITA, KS

SP
CKM 10/25/14