

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-20172-00-00
Spot: NWNWNWNE Sec/Twnshp/Rge: 18-31S-10E
5018 feet from S Section Line, 2261 feet from E Section Line
Lease Name: WILSON L Well #: 2
County: ELK Total Vertical Depth: 2166 feet

Operator License No.: 3591
Op Name: C & E OIL, LLC
Address: RR1 BOX 1B2
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2164		0 SX
SURF	8.625	106		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/09/2014 12:00 AM

Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method:

Surface and production casing unknown. Pump cement for bottom, middle and top plugs per KCC instructions,
--

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 04/30/2014 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Tubing was left in bottom of well. They could only get down to 1970'. On 4/9/2014 Elite Cementing ran 2" to 1970' gelled hole and spotted 15 sacks of 60/40 pozmix. They pulled out and left. On 4/30/2014 Elmore's Inc. perforated casing at 1250' and 550'. Ran 1" to 1250' gelled hole and spotted 10 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 103 sacks of cement were used to plug this well.

Perfs:

RECEIVED

OCT 07 2014

KCC Chanute Dist. #3

DS

Remarks:

Plugged through: TBG

District: 03

Signed

Duane A Sims

(TECHNICIAN)

10.15.14 CKM

Received
KANSAS CORPORATION COMMISSION

OCT 09 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3