

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01446-00-00
Spot: NESWSE Sec/Twnshp/Rge: 4-9S-16W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: HOLY CROSS Well #: 7
County: ROOKS Total Vertical Depth: 3405 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3401		175 SX
SURF	8.625	245		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/07/2014 10:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT Phone: (620) 793-2540

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Tubing and packer stuck at 2400'. Unable to fish. Decided to plug.
LKC perforations: 3148' - 3359'

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/07/2014 3:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Perforated at 800', 1200' and 1800'. Ran tubing to 2268'. Copeland Acid and Cementing pumped 100 sx cement. Pulled tubing to 1255' and pumped 100 sx cement w/200 # hulls. Circulated cement. PTOH. Squeezed 4 1/2" casing w/30 sx cement. Maximum pressure 300 psi. Shut in pressure 300 psi. Hooked up to backside and pumped 5 sx cement. Instant pressure.

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

Received
KANSAS CORPORATION COMMISSION

OCT 14 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed



(TECHNICIAN)

10/15/14 CKM

CM

OCT 09 2014

Form CP-2/3