

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26037-00-00
Spot: N2S2S2NE Sec/Twnshp/Rge: 9-15S-19W
2145 feet from N Section Line, 1320 feet from E Section Line
Lease Name: REICHERT Well #: 1
County: ELLIS Total Vertical Depth: 3755 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: BOX 87
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3755		150 SX
SURF	8.625	232		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/07/2014 9:30 AM
Plug Co. License No.: 34852 Plug Co. Name: NOBLE WELL SERVICE, LLC
Proposal Rcvd. from: BILLY BRINEY Company: NOBLE WELL SERVICE, LLC Phone: (785) 798-5116

Proposed Plugging Method: Ordered 260 sx 60/40 pozmix 4% gel cement, 500 # hulls and 17 sx gel.
PC at 1251' w/200 sx cement
Perforations- 3665' - 3672' and 3666' - 3674'- Laterals.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/07/2014 2:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Noble ran in hole with tubing to 3600' and pumped 17 sx gel followed by 75 sx cement w/200 # hulls mixed in. Pulled tubing to 1350' and pumped 155 sx cement w/300 # hulls to circulate cement to surface. Pulled tubing. Topped off 5 1/2" casing w/20 sx cement. Hole standing full. Rigged to 8 5/8" casing and pumped 10 sx cement w/250 psi. Shut in pressure 250 psi.

GPS: 38.76339 -099.43503

Remarks: GLOBAL CEMENTING CO TICKET # 1462

Plugged through: TBG


Received
KANSAS CORPORATION COMMISSION

OCT 14 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed _____



(TECHNICIAN)

10.15.14 CKM

CM

OCT 09 2014

Form CP-2/3