

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26739-00-00
Spot: W2NWNENE Sec/Twnshp/Rge: 26-15S-18W
330 feet from N Section Line, 1005 feet from E Section Line
Lease Name: LEIKER "A" Well #: 1
County: ELLIS Total Vertical Depth: 3573 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1114		450 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/25/2014 12:00 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: STEVE Company: ROYAL DRILLING INC Phone: (785) 735-4142

Proposed Plugging Method: Ordered 280 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CHRIS NEELEY WitnessType: NONE
Date/Time Plugging Completed: 09/25/2014 4:45 PM KCC Agent: CHRIS NEELEY

Actual Plugging Report: _____ Perfs: _____

1st plug @3510 w/50 sx
2nd plug @1170 w/75 sx
3rd plug @470 w/100 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: QUALITY
Plugged through: DP

Received
KANSAS CORPORATION COMMISSION
OCT 14 2014
CONSERVATION DIVISION
WICHITA, KS

District: 04 Signed Chris Neeley (TECHNICIAN)
10/15/14 CKM

10/09/2014