

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20194-00-00  
Spot: SE Sec/Twnshp/Rge: 14-21S-32W  
1320 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: RAYL Well #: 1-14  
County: FINNEY Total Vertical Depth: 2775 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2758	0	WITH 500 SX CMT
SURF	8.625	360		WITH 300 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/09/2014 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: BUD NEFF Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SQUEEZE PERFS WITH 90 SX CMT & 200# HULLS. TEST CASING TO 700 PSI. RUN CBL TO DETERMINE HOW TO PLUG.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/09/2014 1:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SQUEEZE PERFS WITH 90 SX CMT & 200# HULLS. TEST CASING TO 700 PSI. RUN CBL FOUND TOC @ 100'. RTIH TO 1350' & PUMP 110 SX CMT TO 0'. CHECK BACKSIDE WITH 15 SX CMT TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
2700	2710		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

RECEIVED  
OCT - 8 2014  
KCC DODGE CITY

Signed

Received  
KANSAS CORPORATION COMMISSION

OCT 15 2014  
CONSERVATION DIVISION  
WICHITA, KS  
10/15/14 CKM

(TECHNICIAN)

Form CP-2/3