

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20216-00-00
Spot: SE Sec/Twnshp/Rge: 8-21S-32W
3960 feet from N Section Line, 1320 feet from E Section Line
Lease Name: FAIRLEIGH Well #: 1-8
County: FINNEY Total Vertical Depth: 2680 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2645		WITH 2 SX CMT
PROD	4.5	2675	0	WITH 100 SX CMT
SURF	8.625	346		WITH 550 SX MT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/09/2014 1:30 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: BUD NEFF Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed
Plugging
Method:

SET CIBP @ 2600' WITH 2 SX CMT. RUN CBL TO DETERMINE HOW TO PLUG

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL
Date/Time Plugging Completed: 09/09/2014 6:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 2645' WITH 2 SX CMT. RUN CBL FOUND CMT TO 0'. RTIH TO 1367' &
PUMP 145 SX CMT TO 0'. CHECK BACKSIDE WITH 20 SX CMT TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
2671	2802	OH	

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed

(TECHNICIAN)

RECEIVED

OCT - 8 2014

KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

OCT 15 2014

CONSERVATION DIVISION
WICHITA, KS

10/15/14 CKM

Form CP-2/3