

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20371-00-00  
Spot: SW Sec/Twnshp/Rge: 14-22S-40W  
1319 feet from S Section Line, 3930 feet from E Section Line  
Lease Name: ENGELLAND Well #: 1-14  
County: HAMILTON Total Vertical Depth: 2830 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2824	0	WITH 550 SX CMT
SURF	8.625	370		WITH 275 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/23/2014 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 110 SX CMT WITH 150# HULLS. DISPLACE WITH WATER TO 1100'. TEST CASING TO 700#. RAN CBL TO DETERMINE TOC. PERFORATE AND/OR RUN TBG AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/23/2014 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 110 SX CMT WITH 150# HULLS DOWN 4 1/2" CASING. DISPLACE WITH WATER TO 1300'. PRESSURE TEST CASING TO 600#. HOLDING. RUN CBL FROM 1100' TO 110'. TOC BEHIND 4 1/2" CASING IS 260'. RUN TBG TO 1111'. CIRCULATE CMT TO FILL 4 1/2" CASING TO SURFACE WITH 80 SX CMT. TOOH WITH TBG & TOP OFF 4 1/2" CAISNG WITH 10 SX CMT. PUMP 30 SX CMT DOWN THE ANNULUS TO 200#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2746	2752		


Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

RECEIVED  
OCT - 6 2014  
KCC DODGE CITY

Signed



(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

10/15/14 ckm



OCT 15 2014

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3