

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20706-00-00
Spot: NWSESE Sec/Twnshp/Rge: 12-23S-41W
1250 feet from S Section Line, 1250 feet from E Section Line
Lease Name: BRADSHAW Well #: 3-12
County: HAMILTON Total Vertical Depth: 2625 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2624	0	WITH 150 SX CMT
SURF	8.625	320		WITH 85 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/23/2014 2:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/23/2014 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 170 SX CMT WITH 200# HULLS DOWN 4 1/2" CASING TO 2566'. PRESSURE TO 500#, HOLDING. PUMP 35 SX CMT DOWN THE ANNULUS TO 200#. TOP OFF 4 1/2" CASING WITH 5 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2556	2566		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

OCT 15 2014

CONSERVATION DIVISION
WICHITA, KS

RECEIVED

OCT - 6 2014

KCC DODGE CITY

10/15/14 CKM SP

Form CP-2/3