

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20803-00-00
Spot: SESWNENW Sec/Twnshp/Rge: 2-23S-40W
4030 feet from S Section Line, 3570 feet from E Section Line
Lease Name: BRADDOCK Well #: 3-2
County: HAMILTON Total Vertical Depth: 2800 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2799	0	WITH 610 SX CMT
SURF	8.625	324		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/15/2014 3:30 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 75 SX CMT WITH 300# HULLS & FILL 4 1/2" CASING WITH CMT. ATTEMPT TO PUMP CMT DOWN THE ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/15/2014 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 185 SX CMT WITH 300# HULLS VIA 4 1/2" CASING TO 2638'. PRESSURE TO 400#. HOLDING. PUMP 5 SX CMT DOWN THE ANNULUS TO 400#. HOLDING. TOP OFF 4 1/2" CASING WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2622	2638		

Remarks: **COMPLAINCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed _____

Ken Jehlik
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

OCT 15 2014

CONSERVATION DIVISION
WICHITA, KS

10/15/14 CKM

SP

Form CP-2/3

RECEIVED

OCT -6 2014

KCC DODGE CITY