

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-00849-00-00
Spot: NWNENE Sec/Twnshp/Rge: 1-31S-9W
330 feet from N Section Line, 990 feet from E Section Line
Lease Name: CONRARDY B Well #: 2-1
County: HARPER Total Vertical Depth: 4525 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4523	1670	150 SX
PROD	5.5	4525		150 SXS CMT
SURF	8.625	398		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/11/2014 4:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY Company: ALLIANCE WELL SERVICE Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 09/11/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

SET CIBP @ 4350' CAPPED WITH 2 SXS CEMENT ON TOP. CUT CASING PIPE OFF @ 1670' PULLED CASING. RAN TUBING INTO 1562' SPOTTED 35 SXS CEMENT, 100 LBS HULLS 3% CC, WAITED 2 HOURS TAGGED TOC @ 1050'. RAN TUBING INTO 918' SPOTTED 35 SXS CEMENT. RAN TUBING INTO 459' CIRCUALTED TO SURFACE WITH 180 SXS CEMENT.

Remarks: ALLIED CEMENTNG OUT OF GREAT BEND, COMMON CEMENT USED THROUGH OUT WHOLE JOB
TICKET #064377

Plugged through: TBG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

10/15/14 CKM

Received
KANSAS CORPORATION COMMISSION

OCT 09 2014

CONSERVATION DIVISION
WICHITA, KS