

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-20713-00-00  
Spot: E2NENWNW Sec/Twnshp/Rge: 2-5S-24W  
330 feet from N Section Line, 1000 feet from W Section Line  
Lease Name: JMNJ FARM Well #: 2-2  
County: NORTON Total Vertical Depth: 3950 feet

Operator License No.: 3882  
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN  
Address: 1515 WYNKOOP, STE 700  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	600		300 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/03/2014 12:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS Witness Type: NONE  
Date/Time Plugging Completed: 10/03/2014 7:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st plug @3830 w/50 sx  
2nd plug @2000 w/50 sx  
3rd plug @1400 w/100 sx  
4th plug @650 w/50 sx  
5th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

District: 04

Signed

10/22/14 CKM

(TECHNICIAN)

CM

OCT 15 2014

Received Form CP-2/3  
KANSAS CORPORATION COMMISSION

OCT 21 2014

CONSERVATION DIVISION  
WICHITA, KS