

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-21051-00-00
Spot: SWNWNENW Sec/Twnshp/Rge: 32-17S-33W
4911 feet from S Section Line, 3797 feet from E Section Line
Lease Name: B4US Well #: 1-32
County: SCOTT Total Vertical Depth: 4849 feet

Operator License No.: 7311
Op Name: SHAKESPEARE OIL CO., INC.
Address: 202 W MAIN ST
SALEM, IL 62881

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4250		WITH 2 SX CMT
PROD	4.5	4841	746	WITH 150 SX CMT
SURF	8.625	268		WITH 180 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/25/2014 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/25/2014 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4250' WITH 2 SX CMT. PERFORATE 4 HOLES AT 2440'. INJECTION RATE 1 1/2 BPM @ 600#. PUMP 50 SX CMT HALF IN & HALF OUT OF PERFS AT 2440' @ 400#, 25# HULLS IN LAST HALF. PERFORATE 4 HOLES AT 1460'. INJECTION RATE 2 BPM @ 200#. PUMP 50 SX CMT HALF IN & HALF OUT OF PERFS AT 1460' @ 200#, 25# HULLS IN LAST HALF CMT. CUT CASING AT 746' & PULL TO 740'. SPOT 40 SX CMT. FULL CIRCULATION. PULL TO 270' & CIRCULATE CMT TO SURFACE WITH 150 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4402	4406		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

Received
KANSAS CORPORATION COMMISSION

OCT 20 2014

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

Ken Jehlik

(TECHNICIAN)

10/22/14 ckm

RECEIVED

OCT - 8 2014

KCC DODGE CITY

Form CP-2/3