

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-19032-00-00
Spot: NWSENW Sec/Twnshp/Rge: 23-26S-14E
3350 feet from S Section Line, 3465 feet from E Section Line
Lease Name: LOUK Well #: 2A
County: WOODSON Total Vertical Depth: 1310 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1310		45 SX
SURF	7	198	10	10 SX

Well Type: EOR UIC Docket No: E06103.2 Date/Time to Plug: 09/12/2014 10:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: RICK RICE Company: Phone: (620) 365-3111

Proposed Plugging Method: COMPANY SERVICE UNIT RIN 2" TBG TO BOTTOM. SERVICE COMPANY HOOKED TO 2" & CIRCULATED GEL TO SURFACE. PUMP 300' CMT PLUG ON BOTTOM. COMPANY SERVICE UNIT PULL TBG UP TO 500' SERVICE COMPANY PUMP 50' CMT PLUG AT 500' COMPANY SERVICE UNIT PULL TBG UP TO 250' SERVICE COMPANY PUMP CEMENT FROM 250' TO SURFACE. COMPANY SERVICE UNIT PULL REST OF TBG SERVICE COMPANY TOP WELL OFF. HOOK TO CSG PRESSURE UP SHUT WELL IN. COME BACK LATER DATE & CUT SURFACE CSG OFF "BELOW PLOW DEPTH"

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 09/12/2014 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1290' pumped 300' cement plug , pulled tubing to 500' pumped 50' cement plug, pulled tubing to 300' pumped 255 sxs cement to surface, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1258	1276		
1229	1269		

RECEIVED

OCT 13 2014

KCC Chanute Dist #3

MH

Received
KANSAS CORPORATION COMMISSION

Remarks:

Plugged through: TBG

OCT 16 2014

CONSERVATION DIVISION
WICHITA, KS

District: 03

Signed M. Heffern
(TECHNICIAN)

cc: uic ✓

10/17/14 CKM