

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-02100-00-00  
Spot: NENWNWNE Sec/Twnshp/Rge: 30-26S-17E  
5203 feet from S Section Line, 2033 feet from E Section Line  
Lease Name: HEGWALD Well #: 2 (10)  
County: WOODSON Total Vertical Depth: 850 feet

Operator License No.: 34200  
Op Name: HEGWALD, JACOB L.  
Address: 303 NEW YORK  
HUMBOLDT, KS 66748

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.375	840		132 SX
SURF	7	21		6 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/08/2014 12:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: KEPLEY WELL SERVICE Company: \_\_\_\_\_ Phone: (620) 431-9212

Proposed  
Plugging  
Method:

Pump cement through 1" pipe from bottom to surface. Remove 1" pipe and pressure cement into casing.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed: 09/08/2014 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2.375" casing to TD. Ran 1" pipe down the outside of the 2.375" casing and inside the 10" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2.375" casing from TD to surface. Pumped and circulated cement through the 1" pipe outside the 2.375" casing from TD to surface. Pulled both strings of 1" pipe and topped the well off with cement. A total of 97 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED

OCT 13 2014

KCC Chanute Dist #3

RD

Received  
KANSAS CORPORATION COMMISSION

OCT 16 2014

CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]  
10/17/14 CKM (TECHNICIAN)