

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-11072-00-01

Spot: NENESE

Sec/Twnshp/Rge: 22-34S-2E

2310 feet from S Section Line, 330 feet from E Section Line

Lease Name: THIESSEN

Well #: 3

County: SUMNER

Total Vertical Depth: 3491 feet

Operator License No.: 33405

Op Name: ANSTINE & MUSGROVE INC.

Address: PO BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3462		100 SX
SURF	8.625	102		90 SX

Well Type: EOR

UIC Docket No: E04601.1

Date/Time to Plug: 08/20/2014 8:00 AM

Plug Co. License No.: 31539

Plug Co. Name: SAMS WELL SERVICE, INC.

Proposal Rcvd. from: GARY ANSTINE

Company: ANSTINE & MUSGROVE INC.

Phone: (620) 441-8165

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 08/20/2014 11:30 AM

KCC Agent: DAN FOX

Actual Plugging Report:

BECAUSE OPERATOR COULD NOT GET PAST 2,450' ...PLUGGING INSTRUCTIONS WERE GIVEN BY DISTRICT SUPERVISOR AND WERE CONDUCTED AS FOLLOWS: ON 8/20/2014 @ 8:30 AM OPERATOR PERFORATED 4 SHOTS IN 5.5" AT 2360' THEN RAN IN WITH TUBING AND PUMPED 50 SXS OF CLASS A CEMENT, THEN SQUEEZED 1 BBL OF WATER INTO PERFS, FOR BACKSIDE, WAITED THEN TAGGED AT 2103'. RAN BACK IN TO 369' AND CIRC AMOUNT TO SURFACE WITH 50 SXS OF CLASS A W/2% CC. CONSOLIDATED CEMENT CO. OUT OF CHANUTE KS. TICKET #46464...

Perfs:

Top	Bot	Thru	Comments
2360	2361	TBG	

Remarks: BACKSIDE OF 5 1/2" CEMENTED FROM 327' TO SURFACE ON 6-7-1984.

Plugged through: TBG

District: 02

Signed

CC: UIC ✓

(TECHNICIAN)

10/22/14 CKM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

OCT 21 2014

CONSERVATION DIVISION
WICHITA, KS