

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01726-00-00  
Spot: NWNENE Sec/Twnshp/Rge: 19-9S-20W  
4950 feet from S Section Line, 990 feet from E Section Line  
Lease Name: BALTHAZOR Well #: 3  
County: ROOKS Total Vertical Depth: 3791 feet

Operator License No.: 5364  
Op Name: BEREN CORPORATION  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3767		150 SX
SURF	10.75	183		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/26/2014 10:00 AM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: KURT GABLE Company: BEREXCO LLC Phone: (785) 623-0546

Proposed Plugging Method: Ordered 75 sx common cement w/4% CC, 720 sx 60/40 pozmix 4% gel cement and 700 # hulls. Tubing tailpipe stuck in hole at 2500'. Squeezed at 1100' - 1200' and 1332' - 1350'. Casing leak at 1200' - 1568', 17'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/26/2014 3:30 PM KCC Agent: PAT BEDORE

**Actual Plugging Report:**

**Perfs:**

Perforated 2 holes at 1750' and 175'. Ran tubing to 2500' and pumped 75 sx common cement w/4% CC and 50 # hulls. Pulled 30 joints tubing. Let set for 1 hour. Ran tubing back in hole and tagged at 2289'. Pulled to 2260' and pumped 150 sx cement w/300 # hulls. Pulled tubing to 1510' and pumped 125 sx cement w/300 # hulls. Pulled tubing to 1200' and pumped 150 sx cement w/50 # hulls. Pulled all tubing and topped off 7" casing w/25 sx cement. Hooked to 10 3/4" x 7" annulus and pumped 125 sx cement. Shut in pressure 300 psi.

GPS: 39.26307N -099.59048W

Remarks: ALLIED CEMENTING TICKET # 55500

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

10/22/14 CKM

OCT 06 2014

Received  
KANSAS CORPORATION COMMISSION

OCT 17 2014

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3