

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-06954-00-01
Spot: W2NWNW Sec/Twnshp/Rge: 23-14S-14W
4674 feet from S Section Line, 5078 feet from E Section Line
Lease Name: GURNEY A Well #: 3
County: RUSSELL Total Vertical Depth: 3159 feet

Operator License No.: 34912
Op Name: C12 KANSAS OIL, LLC
Address: 1900 WAZEE ST. SUITE 200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	10	824		
PROD	4.5	2932		600 SX
SURF	7	2994		50 SX

Well Type: EOR UIC Docket No: E13980.3 Date/Time to Plug: 10/08/2014 2:30 PM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: AVEN WEAVERLING Company: C-12 KANSAS OIL, LLC. Phone: (785) 623-3221

Proposed Plugging Method: Ordered 150 sx Class A Cement w/4 1/2" cement retainer and 350 sx 60/40 pozmix 4% gel cement.
10/09/2014- Ordered 150 sx 60/40 pozmix 4% gel cement

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/09/2014 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran cement retainer and set at 2285'. Ran tubing and pumped 150 sx Class A Cement in the retainer at 1800 psi. POOH. Perforated at 1425' and 300'. Ran tubing to 2250' and pumped 75 sx cement. Pulled tubing to 1135' and pumped 150 sx cement. Cement circulated out the backside and had colored water out of the 7" casing. Shut in and shut down for the night.
10/09/2014- Tagged cement at 120' in 4 1/2" casing. Filled w/7 sx cement and pressured to 200 psi. Hooked up to 7" casing and pumped 43 sx cement. Circulated cement out of the 10 3/4" casing and out of the ground around well.

GPS: 38.82557 -098.85386

Perfs:

Top	Bot	Thru	Comments
2994	3159		
2382	2388		
2359	2363		

Remarks: QUALITY CEMENTING TICKET # 815

Plugged through: TBG

District: 04

Signed Ray A. Dinkel
cc: ulc ✓
10/22/14 ckm

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

CM

Form CP-2/3

OCT 21 2014

CONSERVATION DIVISION
WICHITA, KS

OCT 15 2014