

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07328-00-00
Spot: NE Sec/Twnshp/Rge: 11-18S-14W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MILLER G Well #: 4
County: BARTON Total Vertical Depth: 3379 feet

Operator License No.: 7023
Op Name: KLIMA WELL SERVICE, INC.
Address: PO BOX 48
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3372		125 SX
SURF	8.625	843		406 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/08/2014 8:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: DENNIS KLIMA Company: KLIMA OIL INC. Phone: (620) 793-8888

Proposed
Plugging
Method:

Ordered 375 sx 60/40 pozmix 4% gel cement, 13 sx gel and 500 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/08/2014 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Perforated at 1450', 840' and 200'. Ran tubing to 3215' and pumped 13 sx gel followed by 50 sx cement w/50 # hulls. Pulled tubing to 1460' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 470' and pumped 50 sx cement. Cement circulated out braden head and backside. 5 1/2" casing broke off and could not get back to braden head. Filled cellar w/10-15 sx cement. Checked on well later that day and cellar stayed full.

GPS: 38.50229 -098.83602

Remarks: COPELAND CEMENTING TICKET # 42444

Plugged through: TBG

District: 04

Signed Ray A. Dinkel
(TECHNICIAN) C M

Received
KANSAS CORPORATION COMMISSION

10/22/14 CCM

Form CP-2/3

OCT 15 2014

OCT 17 2014
CONSERVATION DIVISION
WICHITA, KS