

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-20701-00-01  
Spot: NWSENE Sec/Twnshp/Rge: 25-20S-14W  
1650 feet from N Section Line, 990 feet from E Section Line  
Lease Name: MAYBACH Well #: 1  
County: BARTON Total Vertical Depth: 3613 feet

Operator License No.: 9971  
Op Name: KODIAK PETROLEUM, INC.  
Address: PO BOX 4677  
ENGLEWOOD, CO 80155

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3611		125 SX
SURF	8.625	366		235 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/07/2014 9:00 AM  
Plug Co. License No.: 34821 Plug Co. Name: K & M WELL SERVICE INC.  
Proposal Rcvd. from: STEVE CRAWFORD Company: KODIAK PETROLEUM, INC. Phone: (620) 793-6874

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 600 # hulls and 300 # C.C.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/07/2014 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 650' and 790'. Ran tubing to 3500' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 2250' and pumped 100 sx cement w/200 # hulls. Lost circulation. Pulled tubing to 1200' and shut down to wait on cement. Ran tubing to 1500' and pumped 75 sx cement. Cement circulated. POOH. Hooked to casing and pumped 20 sx cement to 750 psi. Shut in. Braden head found to be full of cement.

GPS: 38.28541 -09881478

Perfs:

Top	Bot	Thru	Comments
3543	3550		
3334	3340		
3314	3318		
3293	3304		

Remarks: QUALITY CEMENTING TICKET # 709

Plugged through: TBG

District: 04

Signed Ray A. Dinkel  
10/22/14 ckm (TECHNICIAN) CM

Received  
KANSAS CORPORATION COMMISSION

OCT 21 2014

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

OCT 15 2014