

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23117-00-00
Spot: W2NENW Sec/Twnshp/Rge: 25-20S-11W
660 feet from N Section Line, 3450 feet from E Section Line
Lease Name: BRYANT Well #: 1-A
County: BARTON Total Vertical Depth: 3254 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3253	2106	125 SX
SURF	8.625	450		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/01/2014 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 500 # hulls, 200 sx common cement, 6 sx CC and 5 sx gel. Operator told casing pulling crew that casing had holes at about 2000'. Thought they could sand off perms and pull casing at about 2000' and start cement at that depth.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/02/2014 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Dropped sand to sand off perforations then ran bailer to check. Sand could not get past 2106'. Pulled stretch on casing and casing parted at 2106'. Pulled casing and ran tubing in to plug. Reached 2100'. Tied to tubing to pump gel spacer and found tubing was plugged. Could not pump gell. Pulled tubing and found bottom joints were plugged with drilling mud. Ran tubing to 1500' and pumped 125 sx common cement w/3% cc and 250 # hulls. Pulled tubing to 750' and shut down for the day.
10/02/14- Tagged cement at 1060'. Ran tubing to 1050' and pumped 5 sx gel. Pulled tubing to 750'. Circulated cement to surface w/210 sx cement w/350 # hulls. Pulled tubing. Hole stayed full.
GPS: 38.28802 -098.49186

Perfs:

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
10/22/14 CKM (TECHNICIAN) CM

OCT 06 2014

Received
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 21 2014

CONSERVATION DIVISION
WICHITA, KS