

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25395-00-00
Spot: SENWSWSW Sec/Twnshp/Rge: 3-20S-11W
825 feet from S Section Line, 388 feet from W Section Line
Lease Name: DPK Well #: 1-3
County: BARTON Total Vertical Depth: 3400 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3396	2025	200 SX
SURF	8.625	348		3505 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/29/2014 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMANN Company: L D DRILLING Phone: (620) 793-3051

Proposed
Plugging
Method:

Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/29/2014 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped off w/5 sx cement. Cut casing at 2025'. Pulled casing to 1450' and pumped 125 sx cement w/200 # hulls. Pulled casing to 920' and pumped 40 sx cement w/100 # hulls. Pulled casing to 600' and pumped 40 sx cement w/100 # hulls. Pulled casing to 430'. Circulated cement to surface w/125 sx cement and 100 # hulls.

GPS: 38.33565 -098.53378

Perfs:

Top	Bot	Thru	Comments
3304	3306		
3118	3123		
3070	3072		
3054	3059		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie

10/22/14 ckm

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

CM

OCT 06 2014

OCT 21 2014

- Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS